



Department of Public Works
Engineering Division

Fact and Details Sheet: Proposed E Wilson Street and E Doty Street Reconstruction - 2024

PROJECT CONTACTS

- » **Project Engineer:** Fadi El Musa Gonzalez
(608) 243-5214, FElmusagonzalez@cityofmadison.com
- » **Sewers Engineer:** Kyle Frank
KFrank@cityofmadison.com
- » **Water Utility Engineer:** Tim Pearson
TPearson@madisonwater.org
- » **Traffic Engineer:** Lukas Collins
LCollins@cityofmadison.com
- » **Construction Inspection:** Shawn Beer
sbeer@cityofmadison.com
- » **Contractor:** RG Huston
bhuston@rghuston.com

Project Details – Proposed Work

Sanitary Sewer: Replace the existing sanitary sewer main and laterals that were installed in the 1910's and 1920's with new PVC pipe. Replacement of sanitary sewer laterals will be from the new main to the property line.

Water Main: Replace water main along E Wilson Street from S Hancock Street to S Franklin Street with ductile iron pipes. Some blocks have 2 existing mains, and on these blocks, disconnect existing services currently connected to older mains and reconnect to newer mains. Replace hydrants and valves as needed.

Storm Sewer: Replace sections of storm sewer and inlets at intersections due to curb relocation. Replace damaged sections as needed.

Street and Sidewalk: Replace all existing pavement within the project limits. Replace all curb and gutter and concrete terrace along E Wilson Street. Replace damaged sections of curb, gutter and concrete terrace or as needed to complete the replacement of a sanitary sewer lateral along E Doty Street. Install off-street, 2-way cycle track along the south side of E Wilson Street. Replace pedestrian ramps at intersections not meeting A.D.A. and City design standards. Install new pavement markings along sections with new pavement, and install new pavement markings on W. Wilson between S. Carroll St. and MLK Blvd. to connect the existing end of the on-street cycle track to the new off-street cycle track.

Streetlights & Traffic Signals: Existing streetlights will be replaced. New pedestrian scale lighting will be installed mid-block and replaced where existing. Traffic Signal infrastructure and equipment at Wilson/King/Butler intersection will be replaced.

Parking: on-street parking will be permanently removed along the south side of E Wilson Street from S Butler Street to S Franklin Street and 4 on-street parking stalls will be permanently removed along the south side of E Wilson Street west of the S Pinckney Street intersection.

Metro Boarding pads: Install new boarding pads along the street at the following addresses:

- 155 E Wilson Street
- 235 King Street

Construction Schedule and Impacts

Construction Schedule: Construction is expected to begin on May 28, 2024 and be completed by mid-November, 2024. The project will be split into 2 phases of construction. Phase 1 includes E Doty St. from M.L.K. Jr Blvd to King St., E Wilson St. from M.L.K. Jr Blvd to S Pinckney St., and E Wilson St. from King St. to S Franklin St. Phase 2 includes E Wilson St. from S Pinckney St. to King St. and any remaining items to be installed along E Wilson St. from King St. to S Franklin St. Completion of Phase 1 is scheduled for mid-August, 2024. Phase 2 and remaining items under phase 1 should be completed by mid-November, 2024.

The city contractor will begin work on phase 1 along E Doty St. on May 28, 2024. Portions of E Wilson St. within phase 1 will start at a later date. The contractor will notify the City in advance of when work along E Wilson St. within phase 1 construction will start and such information will be provided to the public as an update on the project website. The tentative completion time for work along E Doty St. is scheduled for mid-August. Please note that while the city contractor is working on E Doty St, MG&E will have a contractor on-site working on the installation of underground facilities. Completion of work can be delayed pending on MG&E's progress on their facilities installation. In addition, please note that MG&E may begin construction work along E Doty St. prior to the city project start date.

Construction of Phase 2 will begin mid-August 2024, following completion of Phase 1. Under phase 2 construction work, MG&E will also have a contractor on-site working on replacing existing underground facilities.

Traffic Impacts: Phase 1 construction along E Doty St. will provide 1 travel lane eastbound throughout construction. The remaining lanes, including bike lanes and on-street parking, will be unavailable due to construction activities. Phase 1 construction along E Wilson St. from MLK Jr Blvd. to S Pinckney St. will provide 1 travel lane on the westbound direction and the remaining lanes will be closed for construction. Phase 1 construction along E Wilson St. from King St. to S Franklin St. will provide 2 travel lanes, one in each direction and will have on-street parking unavailable during construction.

Phase 2 of construction along E Wilson St. from S Pinckney St. to King St. will be closed to thru traffic and only local traffic will be allowed. Phase 2 construction along E Wilson St. from King St. to S Franklin St. will provide 2 travel lanes, one in each direction, and will detour westbound traffic into King St, then left turn into E Doty St. (prohibited route under normal conditions), then left turn into S Pinckney St., then right turn into E Wilson St.

Additional traffic detours, if needed, will be announced on the project website. Access to properties within the project limits will be maintained throughout the project duration. Minor access interruptions are expected while the contractor is replacing underground utilities immediately adjacent to a driveway.

Refuse Collection & Mail Delivery: It will be the contractor's responsibility to allow for refuse collection and mail delivery to continue during construction. If applicable to your property, please mark your address on your cart to make sure it is returned if moved. We ask that you place your carts at the street the evening prior to or at the very latest 6:00 a.m. the morning of your scheduled refuse/recycling day.

Project Website: www.cityofmadison.com/WilsonEastDotyEast

Project Limits

